



Rig 14

RIG #14

Rated Drill Depth : 8,000 ft
Rig Type : Mobile Land

Drawworks : Skytop Brewster RR-850 DH 800 HP

Mast : Telescopic Skytop Brewster 410,000 lbs GNC (10 lines) 115 ft Substructure : 388,000 GNC x 17.6 ft of high (RT-GL), 14.2 ft (Below RT-GL)

Capable to perform workover/completion on geothermal well by using

additional pony sub to elevate rotary table 24 ft above GL, 20.6 ft (Below RT-GL)

Engines : 2 unit GM 12V-71, 400 HP each (one unit for back up)

Generators : 3 x CAT D379 - 600 KW each

SCR System : Mud pumps, Drawwork is driven directly by each engine c/w MCC Electric Panel Shack

Rotary Table : 27 1/2" maximum table opening
Hoisting Equipment : Travelling Block, IDECO MFC, 250 tons

Pumps : 3 Unit Triplex Pump 8P-80 Model, 800 HP driven by CAT D-398

BOP EQUIPMENT : 21 1/4"- 2,000 psi annular

13 5/8"- 5,000 psi annular

13 5/8" - 5,000 psi two (2) single RAM

Mud Tank Capacity : 900 bbls capacity Solid Control : 2 Unit Shale Shaker.

Manufacture by MI-Swaco.

Model Mongoose, Provide with 2 Vibrator Motor.

Capable of Handling 10.0 ppg of mud.

16 ea 4" cones desilter 2 ea 10" cones dessander

1 unit Degasser, Manufacture by MI-Swaco

Drill Pipe : 4 1/2" Drill Pipe and 3 1/2" Drill Pipe

Camp : 120 persons

Transportation : 2 x CAT 950 Forklift

1 x Oilfield Winch Truck

2010 - Fully recondition and rebuilt to full standard of OEM

PT Apexindo Pratama Duta Tbk

Head Office : Office 8 20th – 21st Floor, SCBD Lot 28 JL. Jend. Sudirman Kav. 52-53 , Jakarta 12190

Tel. (62-21)29333000 , 29333020 (Hunting) Fax. (62-21) 29333111

Email: info@apexindo.com

Branch Office : Jl. Jend. Sudirman, Balikpapan Permai Complex, Blok L No. 10-12, Balikpapan 76114

Tel. (62-542) 410 258 (Hunting) Fax. (62-542) 411 788

www.apexindo.com