



Rig 4

RIG #4

Rated Drill Depth	: 15,000 ft
Drawworks	: OWI I500 Combined 1,750 HP (Max) 1-3/8" Line
Mast	: Skytop Brewster 1,000,000lbs 142 ft Mast Height
Crown / Floor Saver	: Electronic Mustang Controls Crown/Floor Alert System Crown-O-Matic Toggle Crown Saver and secondary
Substructure	: Skytop Brewster 500,000 lbs setback Box on Box 32 ft KB-Gnd
Engines	: 4 x Caterpillar 3512B 1450HP@1200RPM
Generators	: 4 x AC 1225 KW (17750 KVA) each
SCR System	: M&I 5 Bay SCR
Rotary Table	: National / Varco C-375 650T 37 ½ inch 750hp Independent Electric Motor
Hoisting Equipment	: Gardner Denver 550 ton
Top Drive	: Varco TDS-11S 500T
Pumps	: 3 x Gardner Denver PZL-11 Mud Pumps 1,600 HP Each with 2 x 1,000 HP DC Motors
BOP Equipment	: 29 ½" x 500 psi diverter 21-1/4" x 2,000 psi annular 13.5/8" x 5,000 psi annular 13.5/8" x 5,000 psi double ram 21.1/4" x 2,000 psi double ram
Mud Tank System	: 1,854 bbl system/Brandt Mud Agitators
Solid Control	: 4 x Derrick Flowline Shale Shakers; 12 x Cones Desilter/Mud Cleaner; 2 x Cones Dessander
Drill Pipe	: 5" NC50 Drill Pipe / 3 1/2" NC38 Drill Pipe (15,000 ft 5" Drill pipe, 5,000 ft 3 1/2" Drill Pipe)
Camp	: 200 Man Base Camp + Rig Site Mini Camp
Warehouse	: 2x40' Containers + 8x20' Containers w/ Office

PT Apexindo Pratama Duta Tbk

Head Office : Office 8 20th – 21st Floor, SCBD Lot 28 Jl. Jend. Sudirman Kav. 52-53 , Jakarta 12190
Tel. (62-21)29333000 , 29333020 (Hunting) Fax. (62-21) 29333111
Email: info@apexindo.com

Branch Office : Jl. Jend. Sudirman, Balikpapan Permai Complex, Blok L No. 10-12, Balikpapan 76114
Tel. (62-542) 410 258 (Hunting) Fax. (62-542) 411 788

Contact Person : Donald Kent Wood (Director/ Independent Director)

www.apexindo.com